

Name of Project : RE – ROOFING OF THE SCHISTOSOMIASIS HOSPITAL MAIN BUILDING
Location : Schistosomiasis Hospital, Palo, Leyte

SCOPE OF WORK

I. General Requirements

- Mobilization / Demobilization
- Provision of Safety Warning Signages

II. Project Signboard

- Provision & Installation of Project Signboard
- Provision & Installation of Brass Marker

III. Scaffoldings

- Erection of Scaffoldings, Staging and Support.

IV. Removal of Existing Roofing Structures

- Removal of the Existing Roofing, Ceiling Joists, Trusses, Purlins and other obstructing structures.
- Proper segregation and compilation of the removed materials.

V. Roof System Works

- Provision, Fabrication and Installation of 1/4" x 2" x 2" x 6.0m Angle Bars for Top and Bottom Chord and Web Members of Trusses and 6.0m x 10mm dia. RSB Sagrod.
- Provision and Installation of 2" x 4" x 6.0m x 1.1mm Thk. C- purlins and 2" x 6" x 6.0m x 1.1mm Thk. C- purlins spaced @ 0.60m o.c.
- Provision and Installation of 4' x 8' x 8mm Gusset Plate (Full Weld).
- Provision and Installation of 3/16" x 2" x 2" x 6.0m Angle Bar (Cleats).

VI. Roofing System

- Provision and Installation of 0.40mm Thk x 12'. Pre-painted, Longspan Rib Type Shts., 0.40mm Thk x 8' Pre-fabricated, Pre-painted End Flashing, 0.40mm Thk. X 8' Pre-fabricated, Pre-painted Metal Fascia Board, 0.40mm Plain G.I. Pre-Painted Ridge Roll, 0.40mm Thk. X 8' Pre-painted Spanish Gutter and 0.40mm x 4' x 8' Pre-painted Plain G.I. Sheet and other roofing accessories necessary to complete the work.
- Provision and Installation of Roofing Insulation (One side Aluminum).

VII. Ceiling Works (*interior & exterior ceiling*)


- Provision, Fabrication and installation of 1/4" x 0.60m x 0.60m PVC Laminated Board on 1 1/2" x 1 1/2" x 12 ft Main Runner T-bar, 1 1/2" x 1 1/2" x 2 ft. Cross T-bar and 1 1/2" x 1 1/2" x 12 ft Wall Angle Ceiling Joists spaced at 0.60m x 0.60m o.c. bothways for interior and exterior ceiling.
- Provision and installation of Air Vent and other accessories to complete the work.

Name of Project : RE - ROOFING OF THE MAIN BUILDING AT SCHISTOSOMIASIS HOSPITAL
Location : Schistosomiasis Hospital, Palo, Leyte


VIII. Electrical Works

- Interior Rough-ins: Laying of Electrical Wires, Pipes & fittings
- Provision & Installation of Electrical Fixtures and Accessories: Panel Board with Circuit Breakers, Switches, Convenience Outlets, Lighting Fixtures; Compact Fluorescent Lamp (CFL) and other accessories as indicated in the drawings.


Prepared by:


ENGR. MARC O. YANCHA
Engineer I (J.O.)

Checked by:


ENGR. NOEL ANGELO GALBAN
Engineer II

Approved by:


ENGR. CONRADO M. FUENTES
DOH - Engineer III